



IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

_____ x

In re Application of: :
T. Takabayashi et al. : Art unit: 2853
Serial No. 10/621,635 :
Filed: July 17, 2003 :
For: CONSERVATION METHOD OF :
INK FOR INK-JET :
RECORDING AND IMAGE :
FORMING METHOD :
_____ x

DECLARATION

Honorable Commissioner of Patents
and Trademarks
Washington, D.C. 20231

Sir:

I, Fumio ISHII hereby declare and say as follows:

I am familiar with both the English and Japanese languages and I have compared the annexed English translation with the Japanese text of Japanese Patent Application No. 215164/2002.

To the best of my knowledge and belief, the annexed English translation is an accurate translation of the above Japanese application.

The undersigned declares further that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with

the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both under Section 1001 of Title 18 of the U.S. Code and that such willful false statements may jeopardize the validity of the above-identified application or any patent issuing thereon.

A handwritten signature in cursive script, appearing to read 'F. Ishii', is written above a horizontal line.

Fumio ISHII

Dated: This 26th day of April, 2005.



Patent Application No. 215164/2002

Title of the Document: APPLICATION FOR PATENT

Reference Number: DKT2469450

Address: The Director General of the
Patent Office

**International
Patent Classification:** B41J 2/01
C09D 11/00

Inventor(s) ;

Post-Office Address: C/O Konica Corporation
1 Sakura-machi, Hino-shi,
Tokyo, Japan

Name: Toshiyuki TAKABAYASHI

Applicant for patent:

Identification Number: 000001270

Name: Konica Corporation

Representative: Fumio IWAI

Indication of Fee:

**Prepayment Registration
Number:** 012265

Amount of Payment 21000

List of Documents Attached:

Title of Document:	Specification	1
Title of Document:	Drawings	1
Title of Document:	Abstract	1

Necessity of Proof

Required



[NAME OF DOCUMENT] SPECIFICATION

[TITLE OF THE INVENTION]

CONSERVATION METHOD OF INK FOR INK-JET RECORDING AND
IMAGE FORMING METHOD

[WHAT IS CLAIMED IS:]

[Claim 1] A conservation method of the ink for ink-jet recording which is characterized in that: the ink is an ink for active ray curing type ink-jet recording including a cation polymerization monomer and an initiator, and it is sealed in a container under the condition that the measured percentage of water content by Karl-Fischer method is 1.50 - 5.00 mass %.

[Claim 2] A conservation method of the ink for the ink-jet recording according to (1), wherein the ink includes at least one kind of oxetane compound as the cation polymerization monomer.

[Claim 3] A conservation method of the ink for the ink-jet recording according to (1) or (2), wherein the ink includes a compound having at least one kind of oxirane group.

[Claim 4] In an image forming method by which the printing is conducted onto the recording material by jetting the active ray curing type ink conserved by the conservation

method of the ink for ink-jet recording according to any one of (1) - (3) by the ink-jet recording head, the image forming method is characterized in that: after the ink impacts, the active ray is irradiated during 0.001 - 2.0 sec.

[Claim 5] In an image forming method by which the printing is conducted onto the recording material by jetting the active ray curing type ink conserved by the conservation method of the ink for ink-jet recording according to any one of (1) - (3) by the ink-jet recording head, the image forming method is characterized in that: the total ink film thickness after the ink impacts and is cured by the irradiation of the active ray is 2 - 20 μm .

[Claim 6] In an image forming method by which the printing is conducted onto the recording material by jetting the active ray curing type ink conserved by the conservation method of the ink for ink-jet recording according to any one of (1) - (3) by the ink-jet recording head, the image forming method is characterized in that: the ink liquid drop amount jetted from each nozzle of the recording heads is 2 - 15 pl.

[Claim 7] In an image forming method by which the printing is conducted onto the recording material by jetting the active ray curing type ink conserved by the conservation method of the ink for ink-jet recording according to any one

of (1) - (3) by the ink-jet recording head, the image forming method is characterized in that: the recording head and the ink are heated at the 35 - 100 °C, and the ink is jetted.

[Claim 8] In an image forming method by which the printing is conducted onto the recording material by jetting the active ray curing type ink conserved by the conservation method of the ink for ink-jet recording according to any one of (1) - (3) by the ink-jet recording head, the image forming method is characterized in that: the active ray is irradiated on the ink which impacts on the recording material, and the ink which impacts on the recording material is heated.

[Claim 9] An image forming method according to any one of (4) - (8), wherein the recording material is non-absorptive material.

[Claim 10] An image forming method according to (9), wherein the surface energy of the non-absorptive material is $3.5 - 6.0 \times 10^{-2} \text{ Nm}^{-1}$.

[DETAILED DESCRIPTION OF THE INVENTION]

[0001]

[TECHNICAL FIELD TO WHICH THE INVENTION BELONGS]

The present invention relates to a conservation method of the ink for ink-jet recording by which the high minute

image can be stably reproduced on various recording materials, and to an image forming method.

[0002]

[PRIOR ART]

Recently, because the ink-jet recording method can produce an image simply and at low cost, it is applied to various printing fields such as the photography, each kind of printing, and special printing such as marking and color filter. Particularly, for the recording apparatus by which a fine dot is jetted and controlled, the ink whose color reproduction area, durability, and jetting property are improved, and an exclusive use sheet in which the absorptivity of the ink, coloring property of the coloring material, surface glossiness are greatly increased, are used, and the image quality equal to the silver halide photograph can be obtained.

The increase of the image quality of today's ink-jet recording system is attained only when all of the recording apparatus, ink, and exclusive use sheet are present.

[0003]

However, in the ink-jet system for which the exclusive use sheet is necessary, the recording medium is limited and the cost up of the recording medium become a problem.

Accordingly, many trials to record onto the transferred medium different from the exclusive use sheet by the ink-jet system are made. Specifically, a phase change ink-jet system in which a solid wax ink is used in a room temperature, a solvent series ink-jet system in which the ink in which a quick dry type organic solvent is a main component, is used, or a UV ink-jet system in which, after the recording, a bridge is formed by the ultra violet (UV) ray.

[0004]

Among the above-mentioned trials, the UV ink-jet system is comparatively low odious smell comparing to the solvent series ink-jet system, and for the point which can record onto the recording medium not having the quick dry property and ink absorptivity, it is being remarked recently. Listed examples are, for example, in Japanese Patent Publication Open to Public Inspection (hereafter is called as JP-A) No. 5-54667, JP-A No. 6-200204, and Japanese Translated PCT Patent Publication No. 2000-504778, the ultraviolet ray curing type ink-jet ink is disclosed.

[0005]

However, even when these inks are used, because a dot diameter after an ink impact is largely changed due to the kind of the recording material or the working environment, it

is impossible to form the highly minute image onto various recording materials.

[0006]

For example, as the ultraviolet ray curing type ink, there are a radical polymerization type ultraviolet ray curing type ink centering around the acrylic component and a cation polymerization type ultraviolet ray curing type ink. The radical polymerization type ultraviolet ray curing type ink has a problem in which, in its polymerization mechanism, the curing property is decreased because it is subjected to the oxygen inhibition action under the environment in which the oxygen is present. On the one hand, although the cation polymerization type ultraviolet ray curing type ink is not subjected to the oxygen inhibition action, in the nature of the polymerization reaction, there is a problem in which it is easily subjected to the influence of water(humidity) of the molecular level, and the dark reaction is easily advanced, and there is a problem in the conservation quality.

[0007]

[PROBLEMS THAT THE INVENTION IS TO SOLVE]

In view of the above-described problems, the present invention is attained, and the object of the present invention is to provide a conservation method of the ink for

the active ray curing type ink-jet recording and an image forming method in which the character quality is excellent, color mixing is not generated, and by which a high minute image can be very stably recorded.

[0008]

[MEANS FOR SOLVING THE PROBLEMS]

The above-described objects of the present invention are attained by the following structures.

[0009]

(1) A conservation method of the ink for ink-jet recording which is characterized in that: the ink is an ink for active ray curing type ink-jet recording including a cation polymerization monomer and an initiator, and it is sealed in a container under the condition that the measured percentage of water content by Karl-Fischer method is 1.50 - 5.00 mass %.

[0010]

(2) A conservation method of the ink for the ink-jet recording according to (1), wherein the ink includes at least one kind of oxetane compound as the cation polymerization monomer.

[0011]

(3) A conservation method of the ink for the ink-jet recording according to (1) or (2), wherein the ink includes a compound having at least one kind of oxirane group.

[0012]

(4) In an image forming method by which the printing is conducted onto the recording material by jetting the active ray curing type ink conserved by the conservation method of the ink for ink-jet recording according to any one of (1) - (3) by the ink-jet recording head, the image forming method is characterized in that: after the ink impacts, the active ray is irradiated during 0.001 - 2.0 sec.

[0013]

(5) In an image forming method by which the printing is conducted onto the recording material by jetting the active ray curing type ink conserved by the conservation method of the ink for ink-jet recording according to any one of (1) - (3) by the ink-jet recording head, the image forming method is characterized in that: the total ink film thickness after the ink impacts and is cured by the irradiation of the active ray is 2 - 20 μm .

[0014]

(6) In an image forming method by which the printing is conducted onto the recording material by jetting the active

ray curing type ink conserved by the conservation method of the ink for ink-jet recording according to any one of (1) - (3) by the ink-jet recording head, the image forming method is characterized in that: the ink liquid drop amount jetted from each nozzle of the recording heads is 2 - 15 pl.

[0015]

(7) In an image forming method by which the printing is conducted onto the recording material by jetting the active ray curing type ink conserved by the conservation method of the ink for ink-jet recording according to any one of (1) - (3) by the ink-jet recording head, the image forming method is characterized in that: the recording head and the ink are heated at the 35 - 100 °C, and the ink is jetted.

[0016]

(8) In an image forming method by which the printing is conducted onto the recording material by jetting the active ray curing type ink conserved by the conservation method of the ink for ink-jet recording according to any one of (1) - (3) by the ink-jet recording head, the image forming method is characterized in that: the active ray is irradiated on the ink which impacts on the recording material, and the ink which impacts on the recording material is heated.

[0017]

(9) An image forming method according to any one of (4) - (8), wherein the recording material is non-absorptive material.

[0018]

(10) An image forming method according to (9), wherein the surface energy of the non-absorptive material is $3.5 - 6.0 \times 10^{-2} \text{ Nm}^{-1}$.

[0019]

The present invention will be detailed below. The active ray curing type ink for ink-jet recording used in the present invention is sealed in the container under the condition that the measured percentage of water content by the Karl-Fischer method is 1.50 - 5.00 mass % and conserved. For example, when the ink is sealed in the container under the high humidity of 20 °C, 80 % RH, the percentage of water content within the above range can be attained, however, it is not limited to this. When it is lower than 1.50 mass %, the diversion of the ink viscosity becomes large by the conservation, and the jetting from the recording head is not stable. Particularly, when the ink liquid drop amount is small, the condition is severe. When it is higher than 5.00 mass %, the curability becomes greatly poor. Particularly, for the increase of the image quality, when it is desired to

cur the ink just after the ink impacts on the recording material, the condition becomes severe.

[0020]

When the active ray curing type ink including the cation polymerization monomer conserved within the range of the above percentage of water content and the initiator is used, the high minute image can be stably formed without being influenced by the conservation environment (temperature and humidity) of the ink and the printing environment (temperature and humidity). Further, it is preferable in the point in which the effect of the present invention is more satisfied that an ink supply system from an ink container to the recording head is made a sealing system.

[0021]

Further, as the cation polymerization monomer, when the oxetane compound is included, the control of the percentage of the water content at the time of the ink conservation is specially effective. When the oxetane compound and the compound having the oxetane group are jointly used together, it is more effective.


[0022]

As the initiator, for example, the compound used for the chemical amplification type photo resist or optical

cation polymerization is used ("Organic material for imaging" edited by the organic electronics material study group, Bunshin publication co. (1993), refer to pages 187 - 192, photo-acid generator introduced in "Photo-curing engineering" 2001, by the engineering information association). Examples of the compounds adequate for the present invention will be listed below. Firstly, $B(C_6F_5)_4^-$, PF_6^- , AsF_6^- , SbF_6^- , $CF_3SO_3^-$ salt of the aromatic onium compound such as diazonium, ammonium, iodonium, sulfonium, can be listed. As anti-anion, a compound having a borate compound is preferable because the acid generating ability is high. Specific examples of the onium compounds will be shown below.

[0023]

[Chem 1]




[0024]

Secondly, the sulfonation compound generating the sulfonic acid can be listed. Specific compounds will be illustrated below.

[0025]

[Chem 2]




[0026]

Thirdly, halogenide which light-generates hydrogen halide may also be used. Specific compounds will be illustrated below.

[0027]

[Chem 3]




[0028]

Fourthly, iron-allene complex can be listed.

[0029]

[Chem 4]



[0030]

It is preferable that the ink of the present invention includes the acid breeding agent which newly generates the acid by the acid generated by the irradiation of the active ray which is well known already including Japanese Tokkaihei No. 8-248561, and No. 9-34106. By using the acid breeding agent, a more increase of the jetting stability can be attained.

[0031]

Next, an oxetane compound used for the ink of the present invention will be described. The oxetane compound is a compound having an oxetane ring, and for example, well known all oxetane compounds as introduced in Japanese Tokkai No. 2001-220526, and No. 2001-310937, can be used.

[0032]

When the compound having oxetane rings not smaller than 5 is used, because the viscosity of the composition becomes

high, the handling is difficult, and because the glass transferring temperature of the composition increases, the stickiness of the obtained cured material becomes insufficient. It is preferable that the compound having the oxetane rings used in the present invention is a compound having 1 - 4 oxetane rings.


[0033]

As a compound having one oxetane ring, compounds shown by General Formula (1) are listed.

[0034]

[Chem 5]

General Formula (1)



[0035]

In General Formula (1), R^1 is hydrogen atom or alkyl group of number of carbons of 1- 6, such as methyl group, ethyl group, propyl group, or butyl group, fluoro alkyl group of number of carbons of 1 - 6, allyl group, aryl group, furyl group or thienyl group. R^2 is alkyl group of number of carbons 1 - 6 such as methyl group, ethyl group, propyl group, or butyl group, alchenyl group of number of carbons 2

- 6 such as 1-propenyl group, 2-propenyl group, 2-methyl-1 propenyl group, 2-methyl-2-propenyl group, 1-buthenyl group, 2-buthenyl group, or 3 buthenyl group, a group having the aromatic ring such as phenyl group, benzyl group, fluoro benzyl group, methoxy benzyl group, or phenoxy ethyl group, alkyl carbonyl group of number of carbons 2 - 6, such as ethyl carbonyl group, propyl carbonyl group, or butyl carbonyl group, alcoxy carbonyl group of number of carbons 2 - 6, such as ethoxy carbonyl group, propoxy carbonyl group, or buthoxy carbonyl group, or N-alkyl carbamoyl group of number of carbons 2 - 6, such as ethyl carbamoyl group, propyl carbamoyl group, butyl carbamoyl group or pentyl carbamoyl group.


[0036]

As the oxetane compound used in the present invention, it is particularly preferable that the compound having one oxetane ring is used, because the obtained composition is excellent in the stickiness and it is excellent in the operability in the low viscosity. Next, as the compound having 2 oxetane rings, compounds shown by the following General Formula (2) are listed.

[0037]

[Chem 6]

General Formula (2)



[0038]


In General Formula (2), R¹ is the same group as R¹ in General Formula (1). R³ is, for example, a linear or branched chain alkylene group such as ethylene group, propylene group or butylene group, linear or branched chain poly (alkylene oxy) group, such as poly (ethylene oxy) group or poly (propylene oxy) group, linear or branched chain unsaturated hydrocarbon group, such as propenylene group, methyl propenylene group or butenylen group, or carbonyl group, or alkylene group including carbonyl group, alkylene group including carboxyl group, or alkylene group including carbamoyl group.

Further, R³ is also a polyvalent group selected from the groups shown by the following General Formulas (3), (4), and (5).

[0039]

(Chem 7)

General Formula (3)




[0040]

In General Formula (3), R^4 is hydrogen atom, or alkyl group of number of carbons 1 - 4 such as methyl group, ethyl group, propyl group, butyl group, alkoxy group of number of carbons of 1 - 4 such as methoxy group, ethoxy group, propoxy group, or butoxy group, halogen atom such as chlorine atom, or bromine atom, nitro group, cyano group, mercapto group, lower alkoxy carboxyl group, carboxyl group, or carbamoyl group.

[0041]

(Chem 8)

General Formula (4)




[0042]

In General Formula (4), R^5 expresses oxygen atom, sulfur atom, methylene group, NH, SO, SO₂, C(CF₃)₂, or C(CH₃)₂.

[0043]

(Chem 9)

General Formula (5)




[0044]

In General Formula (5), R^6 is alkyl group of number of carbons 1 - 4, such as methyl group, ethyl group, propyl group, or butyl group, or aryl group. Numeral n is an integer of 0 - 2000. R^7 is alkyl group of number of carbons 1 - 4, such as methyl group, ethyl group, propyl group, butyl group, or aryl group. R^7 is also a group selected from groups shown by the following General Formula (6).

[0045]

[Chem 10]

General Formula (6)



[0046]


In General Formula (6), R^8 is alkyl group of number of carbons 1 - 4 such as methyl group, ethyl group, propyl group, and butyl group, or aryl group. Numeral m is an

integer of 0 - 100. As a specific example of the compound having 2 oxetane rings, the following compounds are listed.


[0047]

[Chem 11]

Illustrative compound 1



Illustrative compound 2




[0048]

An illustrative compound 1 is, in General Formula (2), a compound in which R^1 is ethyl group, and R^3 is carboxyl group. Further, the illustrative compound 2 is, in General Formula (2), a compound in which R^1 is ethyl group, and R^3 is a compound in which R^6 and R^7 are, in General Formula (5), methyl groups, and numeral n is 1. In the compound having 2 oxetane rings, as the preferable example except the above-described compounds, there are compounds shown in the following General Formula (7). In General Formula (7), R^1 is the same group as the R^1 in General Formula (1).

[0049]

(Chem 12)

General Formula (7)




[0050]

As an example of the compound having 3 - 4 oxetane rings, the compounds shown by the following General Formula (8) are listed.

[0051]

(Chem 13)

General Formula (8)








[0052]

In General Formula (8), R¹ is the same group as R¹ in General Formula (1). As R⁹, for example, a branched chain alkylene group of number of carbons 1 - 12 such as groups shown by the following A - C, branched chain poly (alkylene oxy) group such as group shown by the following D, or branched chain poly siloxy group such as group shown by the following E, are listed. Numeral j is 3 or 4.

[0053]

[Chem 14]

A**B****C****D****E**

[0054]

In above A, R^{10} is the lower alkyl group such as methyl group, ethyl group, or propyl group. Further, in above D, p is 1 - 10.


[0055]

As a specific example of compound having 3 - 4 oxetane rings, the illustrative compound 3 is listed.

[0056]

[Chem 15]

Illustrative compound 3




[0057]

Further, as an example of compound having 1 - 4 oxetane rings except the above-described one, the compound shown by the following F (9) is listed.

[0058]

(Chem 16)

General Formula (9)



[0059]


In General Formula (9), R^8 is the same group as R^8 of General Formula (6). R^{11} is alkyl group of number of carbons 1 - 4 such as methyl group, ethyl group, propyl group or

butyl group, or tri-alkyl silyl group, and r is 1 - 4. As a preferable specific example of the oxetane compound used in the present invention, there are illustrative compounds 4 - 6 shown below.


[0060]

[Chem 17]


Illustrative compound 4



Illustrative compound 5



Illustrative compound 6






[0061]

The production method of the compound having the above-described oxetane ring is not particularly limited, and may follow the conventionally known method, for example, there is the oxetane ring synthesizing method from diol, which is disclosed by Pattison (D.B. Pattison, J. Am. Chem. Soc.,

3455, 79 (1957)). Further, other than this, compounds having 1 - 4 oxetane rings having the high molecular weight of about 1000 - 5000 are also listed. As an examples of these compounds, for example, the following compounds are listed.

[0062]

[Chem 18]



[0063]

In epoxy compounds including oxirane group, the preferable one as aromatic epoxide is polyhydric phenol having at least one aromatic nucleus or di or poly glycidyl ether which is produced by the reaction of its alkylene oxide additive body and epichloro-hydrin, and for example, bisphenol A or di or poly glycidyl ether of its alkylene oxide additive body, and novolak type epoxy resin are listed.

Herein, as the alkylene oxide, ethylene oxide and propylene oxide are listed.

[0064]

As the alicyclic epoxide, compounds including cyclohexene oxide or cyclopentene oxide obtained when compounds having at least one cyclo alkane ring such as cyclohexene or cyclo pentene ring are epoxidized by the adequate oxidation agent such as hydrogen peroxide or peroxy acid are preferable.

[0065]

As a preferable one of aliphatic epoxide, there are aliphatic polyhydric alcohol or di or poly glycidyl ether of its alkylene oxide additive body, and as its representative example, di-glycidyl ether of ethylene glycol, di-glycidyl ether of propylene glycol, or di-glycidyl ether of alkylene glycol such as di-glycidyl ether of 1, 6 hexane diol, poly-glycidyl ether of polyhydric alcohol such as di or tri-glycidyl ether of glycerin or its alkylene oxide additive body, di-glycidyl ether of poly-alkylene glycol such as di-glycidyl ether of polyethylene glycol or its alkylene oxide additive body, di-glycidyl ether of poly-alkylene glycol such as di-glycidyl ether of polypropylene glycol or its alkylene oxide additive body, are listed. Herein, as the

alkylene oxide, ethylene oxide and propylene oxide are listed.

[0066]

In the image forming method of the present invention, when the ink is jetted on the recording material by the ink-jet recording method and the image is drawn, and next the active ray such as ultraviolet ray is irradiated, the ink is cured and the image is formed.

[0067]

As the jetting condition of the ink, it is preferable for the point of the jetting stability that the recording head and the ink are heated at 35 - 100 °C, and the ink is jetted. Because the active ray curing type ink has a large viscosity variation range due to the temperature variation, and the variation of the viscosity largely influences the liquid drop size and the liquid drop jetting speed as it is, and the image quality deterioration is caused, it is necessary that its temperature is kept constant while the ink temperature is risen. As the control width of the ink temperature, it is a setting temperature ± 5 °C, preferably, the setting temperature ± 2 °C, and further preferably the setting temperature ± 1 °C.

[0068]

In the present invention, it is preferable that the total ink film thickness after the ink impacts, and active ray is irradiated and the ink is cured, is 2 - 20 μm . Herein, "total film thickness" means the maximum value of the film thickness of the ink drawn on the recording material, and it means the same even for the mono color, and even when the recording is conducted by the ink-jet recording method such as 2 colors superimposition except that (secondary color), 3-color superimposition (third order color), 4-color superimposition (such as the white ink base). In the active ray curing type ink-jet recording of the screen printing field, the actual situation is that the total ink film thickness exceeds 20 μm , however, in the soft package printing field in which the case where the recording material is thin plastic material is many, because, not only a problem of the curl and wrinkle, there is a problem in which the stiffness and texture of the whole printed matter are changed, it can not be used.

[0069]

Further, in the present invention, it is preferable that the liquid drop amount jetted from each nozzle is 2 - 15

pl. In order to form the high minute image, it is necessary that the liquid drop amount is within this range, however, in the case where the ink is jetted with this liquid drop amount, the jetting stability becomes particularly severe as described above.

[0070]

In the image recording method in the present invention, as the irradiation condition of the generation ray, it is preferable that the active ray is irradiated during the time period of 0.001 - 2.0 sec after the ink impacts, and more preferably, 0.001 - 1.0 sec. In order to form the high minute image, it is particularly important that the irradiation timing is as faster as possible.

[0071]

As an irradiation method of the active ray, its basic method is disclosed in Japanese Tokkaisho No. 60-132767. According to this, the light sources are provided on both sides of the head unit, and the head and the light source are scanned by the shuttle method. The irradiation is conducted after a constant time period after the ink impacts. Further, the curing is completed by another light source which is not accompanied by driving. In USP No. 6,145,979, as the irradiation method, the method using the optical fiber or the

method by which the collimated light source is hit on the mirror surface provided on the head unit side surface and the UV light is irradiated onto the recording section, is disclosed. In the image forming method of the present invention, any one of these irradiation methods can be used.

[0072]

Further, the irradiation of the active ray is divided into 2 stages, and a method by which, initially, the active ray is irradiated for 0.001 - 2.0 sec after the ink impacts by the above-described method, and after all printings are completed, the active ray is further irradiated, is also one of preferable modes. When the irradiation of the active ray is divided into 2 stages, the shrinkage of the recording material caused at the time of the ink curing can be further suppressed.

[0073]

In the image forming method of the present invention, it is preferable for forming the high minute image that the ink composition is jetted on the recording material and drawn by the ink-jet recording method, and next, the active ray such as ultra violet ray is irradiated, and the ink is heated, and cured.

[0074]

Next, an example of the ink-jet recording apparatus according to the present invention will be specifically described. Fig. 1 is a perspective view of the whole of the ink-jet printer having a heating means which can be used in the present invention, Fig. 2 is an outline plan view showing a positional relationship of the ink-jet recording head and the leading edge of the optical fiber, and a positional relationship to the heat plate, Fig. 3 is an outline front view showing a positional relationship of the ink-jet recording head and the leading edge of the optical fiber, and a positional relationship to the heat plate.

[0075]

As shown in Fig. 1, an ink-jet printer 1 is located in the upper position of the printer main body 2, and has a sheet feeding section 4 in which a recording material 3 which is a printing medium, is set, a sheet conveying means, not shown, for conveying the recording material 3 set in the sheet feeding section 4 in the secondary scanning direction (same direction as the sheet conveying direction) of an ink-jet recording head 5 at a predetermined speed, an ink-jet recording head 5 to conduct the printing on the recording material 3 conveyed by the sheet conveying means, an ultra violet ray irradiation apparatus A to irradiate the

ultraviolet ray as the active ray onto the ink impact position of the active ray curing type of the cation polymerization type jetted by this ink-jet recording head 5, a heat plate 9 which is a heating means for heating the active ray curing type ink which impacts on the recording material, and a sheet delivery section 7 to deliver the recording material 3 which is printed by the ink-jet recording head 5.

[0076]

The ink-jet recording head 5 is a serial type on demand type, and provided movably between the right position in Fig. 2 and the left position in Fig. 2 along a guide rod 6a of a head moving means 6 in the primary scanning direction (the direction crossing at right angle of the sheet conveying direction). In the right position in Fig. 2, the moving range of an optical fiber 11b of the left side, and in the left position in Fig. 2, the moving range of an optical fiber 11a of the right side are set in such a manner that they are respectively positioned at least on the outer side of the end of the printing area of the recording material 3. The ink-jet recording head 5 has the ink-jet system 4 nozzle head sections 8a - 8d, and this 4 nozzle head sections 8a - 8d are provided so that they can respectively jet the active ray

curing type ink of cation polymerization type of yellow, magenta, cyan, black, onto the recording material 3. The jetting timing of each of nozzle head sections 8a - 8d is controlled according to the jetting data.

[0077]

In Fig. 1, the ultraviolet ray irradiation apparatus A houses the ultraviolet ray lamp, not shown, and has the ultraviolet ray generating section 10 for generating the ultraviolet ray, and 2-system of optical fibers 11a and 11b for guiding the ultraviolet ray generated from this ultraviolet ray generating section 10, and the leading edges of this 2-system of optical fibers 11a and 11b are fixed on both side positions in the primary scanning direction of the ink-jet recording head 5. The optical fibers 11a and 11b are soft and has flexibility, and corresponding to the movement of the ink-jet recording head 5, when the deflection condition is adjusted, the leading edges of the optical fibers 11a and 11b are moved in the primary scanning direction together with the ink-jet recording head 5.

[0078]

The relationship between the impact position onto the recording material 3 of the active ray curing type ink-jetted from the ink-jet recording head 5, and the irradiation

position of the ultraviolet ray of the optical fibers 11a and 11b will be described below. As shown in Fig. 3, the optical fibers 11a and 11b are provided in such a manner that, when the ink-jet recording head 5 is moved from the right to the left direction, the right side optical fiber 11a scans the impact position just after the ink impact, and when the ink-jet recording head 5 is moved from the left to the right direction, the left side optical fiber 11b scans the impact position just after the ink impact. That is, the optical fibers 11a and 11b are positioned in such a manner that the irradiation in each scanning direction of the ink-jet recording head 5 is made in charge of each of 2-system of optical fibers 11a and 11b.

[0079]

The heat plate 9 is structured as a part of the guide plate by which the recording material 3 of the sheet feeding section 4 is conveying-guided to the sheet delivery section 7 through the printed portion, and is positioned over the downstream of the conveying from the jetting point of the ink-jet recording head 5. The heat plate 9 has the heating element in its inside, and the heat is directly conducted to the closely adhered recording material 3, and the impacted active ray curing type ink is heated.

[0080]

In the above structure, when the cation polymerization type active ray curing type ink is jetted onto the recording material 3 from the ink-jet recording head 5, the ultraviolet ray follows the active ray curing type ink and is irradiated just after its impact (within 10 sec). Further, the impacted active ray curing type ink is heated by the heat of the heat plate 9. As described above, because the impacted active ray curing type ink receives the ultraviolet ray at the higher temperature than a predetermined temperature, the active ray curing type ink is successively cured even under the much humid environment because the curing reaction is activated. Accordingly, even under the much humid environment, by using the cation polymerization type active ray curing type ink, the fine printing can be performed. Further, even when the recording material 3 in which the ink easily bleeds is used, the ink bleeding is not generated, and the printed matter which is strong for rubbing-off can be obtained.

[0081]

In this embodiment, the ultraviolet ray irradiation apparatus A has an ultraviolet ray generating section 10 for generating the ultraviolet ray and the optical fibers 11a and 11b for guiding the ultraviolet ray generated from this

ultraviolet ray generating section 10 to a near position of the ink-jet type head 5, and because the ultraviolet ray is irradiated from the leading edges of these optical fibers 11a and 11b, the ultraviolet ray is irradiated spot-likely onto the ink impact position in the near distance to the recording material 3, therefore, because a predetermined amount of the ultraviolet ray amount can be sufficiently irradiated by the weak ultraviolet ray, a small sized one, and a low cost one are enough for the ultraviolet ray irradiation apparatus A. Further, because it is not necessary that the ultraviolet ray lamp corresponding to the printing width is prepared, and further, it is not necessary that the ultraviolet ray lamp itself is moved, it is excellent also in the points of safety and durability.

[0082]

In this embodiment, because the leading edges of the optical fibers 11a and 11b are fixed on the ink-jet recording head 5, they can be interlocked with the printing speed of the ink-jet recording head 5 and can move in the primary scanning direction so that the impact position can be irradiated just after the active ray curing type ink impacts. Accordingly, it is not necessary that the ultraviolet ray

generating section 10 is moved, but because only the leading edges of the optical fibers 11a and 11b may be moved, the follow irradiation of the ultraviolet ray can be easily conducted. Further, because it is not necessary that the fiber moving means is specially provided for moving the leading edges of the optical fibers 11a and 11b, it contributes to the prevention of the increase of the number of parts or the easiness of the control.

[0083]

In this embodiment, 2 systems of the optical fibers 11a and 11b are provided, and because respective of leading edges of these 2 systems of optical fibers 11a and 11b are arranged on both side positions of the ink-jet recording head 5 in the primary scanning direction, and respective of the 2 systems of the optical fibers 11a and 11b are arranged so that they are in charge of the irradiation in each scanning direction of the ink-jet recording head 5, even in the case where the ink-jet recording head 5 scans in any direction, the ultraviolet ray can be effectively irradiated just after the ink impacts. Accordingly, the active ray curing type ink can be cured without changing the irradiation position of the ultraviolet ray which is irradiated from the leading edges of the optical fibers 11a and 11b.

[0084]

As a modified example of this embodiment, one system of the optical fibers may be provided. However, in the case where it is made correspond to the ink-jet recording head 5 which conducts the printing operation in two ways of the primary scanning direction, it is necessary that the irradiation position of the ultraviolet ray irradiated from the leading edge of the optical fiber is changed so that the ultraviolet ray can be effectively irradiated just after the ink impacts, even in the case where the ink-jet recording head 5 scans in any direction. Hereupon, in the case of the ink-jet recording head 5 which conducts the printing operation only in one direction of the primary scanning direction, of course, it is not necessary that the irradiation position of the ultraviolet ray irradiated from the leading edge of the optical fiber is changed.

[0085]

Further, the ink-jet recording head may also be made a line type on-demand type, and in this case, a moving means for moving the optical fiber in the primary scanning direction is necessary.

[0086]

Further, in this embodiment, although the heating means is structured by a heat plate 9, it may also be structured as a hot air blowing means for blowing the hot air to the active ray curing type ink which impacts on the recording material

3. When it is structured in this manner, the hot air is blown to the impacted active ray curing type ink by the hot air blowing means and the active ray curing type ink is heated. Herein, when the hot air blowing means is structured by introducing the heat generated from the ultraviolet ray generating section 10 to the vicinity of the ink-jet recording head 5 by a tube, it is not necessary that the hot air blowing means is separately provided, and it is preferable for reduction of number of parts, size reduction, and cost reduction.

[0087]

Hereupon, in the above description, although the ink-jet recording head 5 is a head corresponding to the color which has a plurality of nozzle head portions 8a - 8d, the head of monochrome having a single nozzle head can also be used.

[0088]

As a coloring material according to the present invention, the coloring material which can dissolve or

disperse in the main component of the polymerization compound, can be used, however, a pigment is preferable from a point of weather-tightness.

[0089]

The pigments which can be preferably used, will be listed below.

C. I Pigment Yellow - 1, 3, 12, 13, 14, 17, 81, 83, 87, 95, 109, 42.

C. I Pigment Orange - 16, 36, 38

C. I Pigment Red - 5, 22, 38, 48 : 1, 48 : 2, 48 : 4, 49 : 1, 53 : 1, 57 : 1, 63 : 1, 144, 146, 185, 101.

C. I Pigment Violet - 19, 23

C. I Pigment Blue - 15 : 1, 15 : 3, 15 : 4, 18, 60, 27, 29

C. I Pigment Green - 7, 36

C. I pigment White - 6, 18, 21

C. I pigment Black - 7

Further, in the present invention, in order to increase the shielding property of the color in the transparent base material such as the plastic film, it is preferable that the white ink is used. Particularly, in the soft package printing, or label printing, it is preferable that the white ink is used, however, because the jetting amount becomes large, from the viewpoint of the jetting stability, and

generation of the curl and wrinkle, there is naturally a limitation as for the using amount.

[0090]

For the dispersion of the pigment, for example, a ball mill, sand mill, attritor mill, roll mill, agitator, Henshel mixer, colloid mill, ultrasonic homogenizer, pearl mill, wet jet mill, or paint shaker can be used. Further, when the pigment is dispersed, a dispersing agent can also be added. As the dispersing agent, it is preferable that the polymeric dispersing agent is used, and as the polymeric dispersing agent, Solsperse series by AVECIA Co., are listed. Further, as the dispersion auxiliary, a synergist corresponding to each kind of pigment can also be used. In these dispersing agent and dispersion auxiliary, it is preferable that, to the pigment 100 mass part, 1 - 50 mass part is added. As dispersion medium, the dispersion is conducted by using the solvent or polymerization compound, however, it is preferable that the active ray curing type ink used in the present invention is no solvent because it is reacted and cured just after the ink impacts. When the solvent remains on the cured image, a problem of the deterioration of the solvent resistance, and VOC of the remaining solvent is generated. Accordingly, it is preferable in the dispersion property that

the dispersion medium is not the solvent, but the polymerization compounds, and in them, the monomer whose viscosity is lowest is selected.

[0091]

In the dispersion of the pigment, it is preferable that the average particle diameter of the pigment particle is 0.08 - 0.5 μm , maximum particle diameter is 0.3 - 10 μm , and preferably, the selection of the pigment, dispersing agent and the dispersion medium, and the dispersing condition, and filtering condition are set so that maximum particle diameter is 0.3 - 3 μm . By this particle diameter control, the choking of the head nozzle can be suppressed, and conservation stability of the ink, ink transparency and curing sensitivity can be maintained.

[0092]

As the coloring material density of the ink according to the present invention, it is preferable that it is 1 - 10 mass % of the whole ink.

[0093]

In the ink according to the present invention, various additive agents can be used other than the above description. For example, the interface active agent, leveling additive

agent, mat agent, polyester resin to adjust the film physical properties, polyurethane resin, vinyl resin, acrylic resin, rubber resin, or wax can be added. Further, in order to improve the conservation stability, although all well known basic compounds can be used, as representative compounds, the basic alkali-metal compound, basic alkali earth metal compound, basic organic compound such as amine are listed. Further, the radical polymerization monomer and the initiator are combined, and it can also be made the hybrid type cured ink of the radical · cation.

[0094]

As the recording material which can be used in the present invention, other than an ordinary non-coat sheet and coat sheet, each kind of non-absorptive plastic used for so-called soft package and its film can be used, and as each kind of plastic film, for example, PET film, OPS film, OPP film, ONy film, PVC film, PE film, or TAC film can be listed. As the other plastic, polycarbonate, acrylic resin, ABS, polyacetal, PVA, or rubber can be used. Further, it can also be applied to metal or glass. In these recording materials, particularly when the image is formed onto the PET film, OPS film, OPP film, ONy film, PVC film, which are shrinkable by the heat, the structure of the present invention is

effective. In these base materials, not only the curl and deformation of the film are easily generated by the heat generation at the time of curing shrinkage and curing reaction of the ink, but the ink film also hardly follows the shrinkage of the base material.

[0095]

The surface energy of each kind of plastic film is largely different, and conventionally, it is a problem that the dot diameter after the ink impact is changed depending on the recording material. In the structure of the present invention, the good high minute image can be formed on the recording material of the wide range in which the surface energy is $3.5 - 6.0 \times 10^{-2} \text{ Nm}^{-1}$, including OPP film, OPS film, whose surface energy is low, and PET whose surface energy is comparatively large.

[0096]

In the present invention, in the point of the cost of the recording material such as the cost of the package or the production cost, and the production efficiency of the print, and in the point in which it can cope with the print of each kind of size, it is advantageous that the long sized (web) recording material is used.

[0097]

[EXAMPLES]

The present invention is specifically shown below by examples, but the present invention is not limited to them.

[0098]

[Ink composition]

The ink compositions written in Tables 1, 2, 3 are produced, and after the water content is measured by Carl Fisher method as shown in Tables 4, 5, 6, they are sealed in the polyethylene container, and conserved for 2 weeks at 25 °C and 50 °C. The comparative example is sealed under the environment of 20 °C, 40 % RH, and the present invention is sealed under the environment of 30 °C, 80 % RH. The viscosity of the ink composition 1, 2 is 50 mPa. s at 25 °C, and the viscosity of the ink composition 3 is 60 mPa. s at 25 °C.

[0099]

In this connection, the meanings of symbols in the table are as follows.

K: dark black ink, C: dark cyan ink, M: dark magenta ink, Y: dark yellow ink, W: white, Lk: light black ink, Lc: light cyan ink, Lm: light magenta ink, Ly: light yellow ink

Coloring material 1: C. I pigment Black 7

Coloring material 2: C. I Pigment Blue 15 : 3

Coloring material 3: C. I Pigment Red 57 : 1

Coloring material 4: C. I Pigment Yellow 13

Coloring material 5: titanium dioxide (anatase-type:
particle diameter 0.2)

Table 1

Ink composition 1

	K	C	M	Y	W	Lk	Lc	Im	Ly
Coloring material	C 1	C 2	C 3	C 4	C 5	C 1	C 2	C 3	C 4
Coloring material	5.0	2.5	3.0	2.5	5.0	1.3	0.6	0.8	0.6
Photo polymerization compound (*1)	DAIMIC S300K (Daisel chem. co.)	20.0	15.0	15.0	20.0	15.0	15.0	15.0	15.0
Photo polymerization compound (*2)	OXT-211 (TOA GOSEI)	64.4	74.4	73.9	74.4	66.4	75.6	76.1	76.3
Acid breeding agent	ACPRES 11 (NIPPON CHEMIX)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Basic compound	N-ethyl di-ethanol amine	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
Thermal base generating agent	Thermal base 2	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1
Light and thermal acid generating agent	Initiator 1	1.5	1.0	1.0	1.5	1.0	1.0	1.0	1.0
Photo acid generating agent	SP152 (ASAHI DENKA Industry)	5.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Photo acid generating agent auxiliary	CS7102 (NIPPON SODA)	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0

*1: Epoxidation soy bean oil

*2: Oxetane compound

C: Coloring material

Table 2

Ink composition 2

		K	C	M	Y	W	Lk	Lc	Im	Ly
Coloring material		C 1	C 2	C 3	C 4	C 5	C 1	C 2	C 3	C 4
Coloring material		5.0	2.5	3.0	2.5	5.0	1.3	0.6	0.8	0.6
Photo polymerization compound (*3)	EPOREED PB3600 (Daisel chem. co.)	12.4	23.9	23.4	23.9	15.9	25.2	25.8	25.7	25.8
Photo polymerization compound (*4)	OXT-221 (TOA GOSEI)	70.0	65.0	65.0	65.0	70.0	65.0	65.0	65.0	65.0
Acid breeding agent	Compound 1	3.0	1.5	1.5	1.5	1.5	1.5	1.5	1.5	1.5
Thermal base generating agent	Thermal base 1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1
Light and thermal acid generating agent	Initiator 2	1.5	1.0	1.0	1.0	1.5	1.0	1.0	1.0	1.0
Photo acid generating agent	C15102 (NIPPON SODA)	5.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Photo acid generating agent auxiliary	CS7001 (NIPPON SODA)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0

*3: Epoxidation poly-butadiene

*4: Mono-functional oxetane compound

C: Coloring material

Table 3

Ink composition 3

		K	C	M	Y	W	Lk	Lc	Lm	Ly
Coloring material		C 1	C 2	C 3	C 4	C 5	C 1	C 2	C 3	C 4
Coloring material		5.0	2.5	3.0	2.5	5.0	1.3	0.6	0.8	0.6
Photo polymerization compound (*5)	ADEKASIZER-0-130P (ASAHI DENKA Industry)	26.9	24.4	23.9	24.4	26.9	25.6	26.3	26.1	26.3
Photo polymerization compound (*6)	OXT-221 (TOA GOSEI)	60.0	65.0	65.0	65.0	60.0	65.0	65.0	65.0	65.0
Acid breeding agent	compound 2	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Basic compound	N-ethyl di-ethanol amine	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01
Thermal base generating agent	Thermal base 2	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1
Light and thermal acid generating agent	Initiator 3	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5
Photo acid generating agent	Initiator 4	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5

*5: Epoxidation soy bean oil


*6: Mono-functional oxetane compound

C: Coloring material


[0103]

[Chem 19]

Thermal base 1




Thermal base 2




[0104]

[Chem 20]


Compound 1




Compound 2




Initiator 1



Initiator 2



Initiator 3



Initiator 4




Table 4

Sam- ple No.	Ink	Water content (weight%) at the time of ink conservation	Ink conservation temperature (2 weeks) (°C)	Recording material	Surface energy ($\times 10^{-3}$ Nm^{-1})	Recording material surface temperature °C
1	Ink comp. 1	0.8	25	OPP	38	*3 (25)
2	Ink comp. 1	0.8	25	PET	53	*3 (25)
3	Ink comp. 1	0.8	25	shrink OPS	39	*3 (25)
4	Ink comp. 1	0.8	25	*1	*2	*3 (25)
5	Ink comp. 1	0.8	50	OPP	38	*3 (25)
6	Ink comp. 1	0.8	50	PET	53	*3 (25)
7	Ink comp. 1	0.8	50	shrink OPS	39	*3 (25)
8	Ink comp. 1	0.8	50	*1	*2	*3 (25)
9	Ink comp. 1	2.3	25	OPP	38	*3 (25)
10	Ink comp. 1	2.3	25	PET	53	*3 (25)
11	Ink comp. 1	2.3	25	shrink OPS	39	*3 (25)
12	Ink comp. 1	2.3	25	*1	*2	*3 (25)
13	Ink comp. 1	2.3	50	OPP	38	*3 (25)
14	Ink comp. 1	2.3	50	PET	53	*3 (25)
15	Ink comp. 1	2.3	50	shrink OPS	39	*3 (25)
16	Ink comp. 1	2.3	50	*1	*2	*3 (25)
17	Ink comp. 2	1.0	50	OPP	38	*3 (25)
18	Ink comp. 2	1.0	50	PET	53	*3 (25)
19	Ink comp. 2	1.0	50	shrink OPS	39	*3 (25)
20	Ink comp. 2	1.0	50	*1	*2	*3 (25)
21	Ink comp. 2	2.5	50	OPP	38	40
22	Ink comp. 2	2.5	50	PET	53	40
23	Ink comp. 2	2.5	50	shrink OPS	39	40
24	Ink comp. 2	2.5	50	*1	*2	40
25	Ink comp. 3	0.5	50	OPP	38	40

Table 4 (continued)

Sam- ple No.	Ink	Water content (weight%) at the time of ink conservation	Ink conservation temperature (2 weeks) (°C)	Recording material	Surface energy ($\times 10^{-3}$ Nm^{-1})	Recording material surface temperature °C
26	Ink comp. 3	0.5	50	PET	53	40
27	Ink comp. 3	0.5	50	shrink OPS	39	40
28	Ink comp. 3	0.5	50	*1	*2	40
29	Ink comp. 3	2.1	50	OPP	38	40
30	Ink comp. 3	2.1	50	PET	53	40
31	Ink comp. 3	2.1	50	shrink OPS	39	40
32	Ink comp. 3	2.1	50	*1	*2	40

OPP: Oriented polypropylene, ONy: Oriented nylon, PET: Polyester

OPS: Oriented polyester, PVC: Polyvinyl chloride

*1: Cast coat sheet, *2: Absorptive recording material, *3: no heating

[0106]

Table 5

Sample No.	Irradiation condition					Note
	Irradiation light source	Irradiation timing, 0.2 sec later after ink impact	Irradiation manner (area)	Maximum illumination on recording material surface and peak wavelength 650 mW/cm ² at 365 nm	Energy and peak wavelength 180 mJ/cm ² at 365 nm	
1	*6	0.2	*7	650	180	Comp.
2	*6	0.2	*7	650	180	Comp.
3	*6	0.2	*7	650	180	Comp.
4	*6	0.2	*7	650	180	Comp.
5	*6	0.2	*7	650	180	Comp.
6	*6	0.2	*7	650	180	Comp.
7	*6	0.2	*7	650	180	Comp.
8	*6	0.2	*7	650	180	Comp.
9	*6	0.2	*7	650	180	Inv.
10	*6	0.2	*7	650	180	Inv.
11	*6	0.2	*7	650	180	Inv.
12	*6	0.2	*7	650	180	Inv.
13	*6	0.2	*7	650	180	Inv.
14	*6	0.2	*7	650	180	Inv.
15	*6	0.2	*7	650	180	Inv.
16	*6	0.2	*7	650	180	Inv.

*6: 120 W/cm metal halide lamp (by Nippon denchi, MAL 400 NL) 3 kW power source

*7: Both sides of recording head, line light source irradiation

Comp.: Comparative example, Inv.: Present invention

Table 6

Sample No.	Irradiation condition					Note
	Irradiation light source	Irradiation timing, 0.2 sec later after ink impact	Irradiation manner (area)	Maximum illumination on recording material surface and peak wavelength 10 mW/cm ² at 306 nm	Energy and peak wavelength 38 mJ/cm ² at 306 nm	
17	*8	0.2	*9	10	38	Comp.
18	*8	0.2	*9	10	38	Comp.
19	*8	0.2	*9	10	38	Comp.
20	*8	0.2	*9	10	38	Comp.
21	*8	0.2	*9	10	38	Inv.
22	*8	0.2	*9	10	38	Inv.
23	*8	0.2	*9	10	38	Inv.
24	*8	0.2	*9	10	38	Inv.
25	*8	0.2	*9	10	38	Comp.
26	*8	0.2	*9	10	38	Comp.
27	*8	0.2	*9	10	38	Comp.
28	*8	0.2	*9	10	38	Comp.
29	*8	0.2	*9	10	38	Inv.
30	*8	0.2	*9	10	38	Inv.
31	*8	0.2	*9	10	38	Inv.
32	*8	0.2	*9	10	38	Inv.

*8: Cool cathode tube (by Hipec, special order) electric power of power source: not larger than 1 kW·Hr

*9: Both sides of recording head, irradiation by respective 8 line light sources
Comp.: Comparative example, Inv.: More preferable present invention

[0108]

[Ink-jet recording]

By the ink-jet recording apparatus using the piezoelectric type ink-jet nozzle, the image recording is conducted on the recording material of the width of 600 mm having the surface energy written in Table 4. The ink supply system is composed of an ink tank, supply pipe, front chamber ink tank just before the head, piping with a filter, and piezoelectric head. The recording head section is temperature-adjusted to 55 °C. Further, the ink supply system from the ink container to the ink tank and the recording head is made a sealing system. The piezoelectric head is driven so that the multi size dot of 2 - 15 pl can be jetted in the resolution of 720 x 720 dpi (dpi expresses the number of dots per 1 inch, that is, 2.54 cm) and the ink is jetted. The irradiation condition after the ink impact is as shown in Tables 5 and 6. Further, the recording material after the ink impact is heated by the conveying guide plate, and the recording material surface is made as shown in Tables 5 and 6. After the recording, when the total ink film thickness is measured, it is 2.3 - 13 μm .

[0109]

[Evaluation]

The result of the recording under the environment of 10 °C, 20 % RH, the recording under the environment of 25 °C, 50 % RH, and the recording under the environment of 32 °C, 80 % RH is shown in Table 7.

[0110]

[Character quality]

A 6 point MS Minchotai character is printed in each target density of YMCK, and the roughness of the character is enlarged-evaluated by a loupe.

[0111]

A... no roughness

B... roughness is slightly seen

C... roughness is seen, but can be discriminated as the character, and in a level in which it can barely be used

D... much roughness, and in a level in which the character is blurred and can not be used

[Color mixing]

Adjoining each color dot in the printed high minute image is enlarged by the loupe, and the bleeding situation is visually evaluated.

[0112]

A... adjoining dot shape keeps true circle, and no bleeding

B... adjoining dot shape keeps almost true circle, and almost no bleeding

C... adjoining dots are slightly bled and the dot shape is slightly broken, and in a level in which it can be barely used

D... adjoining dots are bled and mixed and in a level in which it can not be used

[0113]

[Table 7]

Sam- ple No.	10 °C, 20 % RH		25 °C, 50 % RH		32 °C, 80 % RH		Note
	Character quality	Color mixing (bleed- ing)	Character quality	Color mixing (bleed- ing)	Character quality	Color mixing (bleed- ing)	
1	B	B	B	B	C	B	*1
2	B	B	B	B	B	C	*1
3	B	B	B	B	C	B	*1
4	B	B	B	B	B	C	*1
5	D	C	D	D	D	D	*1
6	C	D	D	D	D	D	*1
7	D	C	D	D	D	D	*1
8	C	D	D	D	D	D	*1
9	B	B	B	B	B	B	*2
10	B	B	B	C	B	C	*2
11	B	B	B	B	B	B	*2
12	B	B	B	B	B	C	*2
13	B	B	B	B	C	B	*2
14	B	C	B	C	B	C	*2
15	B	B	B	B	C	B	*2
16	B	B	B	B	B	C	*2
17	D	B	D	C	D	C	*1
18	C	C	C	C	C	D	*1
19	C	B	C	B	D	C	*1
20	C	B	C	C	D	D	*1
21	C	B	C	B	B	B	*3
22	B	B	B	A	B	A	*3
23	A	A	A	A	A	A	*3
24	A	A	A	A	A	A	*3
25	C	B	D	C	D	C	*1
26	C	C	C	D	C	D	*1
27	C	B	D	C	D	C	*1
28	C	B	D	C	D	D	*1
29	B	A	B	A	B	A	*3
30	A	A	A	B	A	B	*3
31	A	A	A	A	A	B	*3
32	A	B	A	B	A	B	*3

*1: Comparative example

*2: Present invention

*3: More preferable present invention

[0114]

From Table 7, it is clear that the samples according to the present invention are more excellent than the comparative example in the character quality and the generation of color mixing.

[0115]

[EFFECT OF THE INVENTION]

According to the present invention, the high minute ink-jet image which is excellent in the character quality and in which there is no generation of the color mixing, can be presented.

[BRIEF DESCRIPTION OF THE DRAWINGS]


Fig. 1 is a perspective view of the whole of an ink-jet printer having a heating means which can be used in the present invention.

Fig. 2 is an outline plan view showing the positional relationship between an ink-jet recording head and the leading edge of an optical fiber and the positional relationship with a heat plate.

Fig. 3 is an outline front view showing the positional relationship between an ink-jet recording head and the leading edge of an optical fiber and the positional relationship with a heat plate.

[DESCRIPTION OF THE REFERENCE NUMERAL AND SIGNS]

- 1: ink-jet printer
- 2: printer main body
- 3: recording material
- 4: sheet feeding section
- 5: ink-jet recording head
- 6: head moving means
- 6a: guide rod
- 7: sheet delivery section
- 8a - 8d: nozzle head section
- 9: heat plate
- 10: ultraviolet ray generating section
- 11a, 11b: optical fibers
- A: ultraviolet ray irradiation apparatus



[NAME OF THE DOCUMENT] Drawings

FIG. 1




FIG. 2





FIG. 3



[NAME OF DOCUMENT] Abstract

[ABSTRACT]

[PROBLEM]

To provide a conservation method of the ink for an active ray curing type ink-jet recording and an image forming method, which is excellent in the character quality and can stably record a high minute image.

[MEANS FOR RESOLUTION]

A conservation method of the ink for the ink-jet recording which is characterized in that: in the ink for an active ray curing type ink-jet recording which includes a cation polymerization monomer and an initiator, the ink is sealed in a container under the condition that the measured water content by the Karl-Fischer method is 1.50 - 5.00 mass %.

[SELECTED DRAWING] None